

Proposal

Work to be Completed for The County of San Benito

Work Site: 1111 San Felipe Rd., Suite 102

Scope: Server Room Materials	Hours

Total Hours 0
 Rate Per Hour \$100.00
 Labor Subtotal \$0.00

Materials	Units	Cost/Unit	Total Cost
CPI 2-post 19 inch telecom rack, black	1	\$175.00	\$175.00
CPI 12 inch wall angle support kit, black	2	\$45.00	\$90.00
CPI top plate kit, black	1	\$45.00	\$45.00
* Tripp Lite rack mount fixed shelf 60 lb. capacity (SRSHELF2P)	1	\$65.99	\$65.99
Tripp Lite 25U wall mount open frame rack with square holes (SR4POST25)	1	\$371.99	\$371.99
Panduit 2U, double sided horizontal wire manager	10	\$75.00	\$750.00
Panduit 1U, double sided horizontal wire manager	2	\$55.00	\$110.00
Panduit 7", double sided vertical wire manager	1	\$256.80	\$256.80
Dynacom cat6 48-port patch panel	5	\$225.00	\$1,125.00
APC Smart-UPS X 3000VA Rack LCD UPS w/ network management (SMX3000LVNC)	1	\$1,869.99	\$1,869.99

Materials Subtotal \$4,859.77
 Tax \$413.08
 Shipping \$200.00
Total \$5,472.85



All work will be completed in a professional and timely manner adhering to all local city, county state NEC, NFPA, OSHA and IEEE 802.3 rules and regulations set forth by these organizations.

Please Read

This quote is based on the phone call and email from The County of San Benito on Thursday, November 2nd, 2017. The client has requested materials to build out an IDF room including one 2-post 19 inch rack for network and telephone equipment and one 24U wall mounted rack for all patch panels and wire managers.

* The Tripp Lite fixed shelf is not needed to support any of the network switches so long as all switches have their corresponding mounting brackets. The fixed shelf is listed as an optional item only for any devices that are not rack mountable or that do not have their mounting brackets.